MYSORE RAILWAYS, MYSORE.

MYSORE DIVISION (OPEN LINES.)

Notification, dated 2nd August 1933.

Notice is hereby given that sealed tenders will be received at the Office of the Senior Executive Engineer, Open Line Division, Mysore Railways, Mysore, up to 4 P.M., on the 26th August 1933, from contractors who are willing to do the work of Construction of Pits in the Engine Erection Shop in the Central Workshops area.

2. Every tender must be accompanied by an earnest money of Rs. 300 which should be paid to the Auditor, Mysore Railways, Mysore and the receipt thereof enclosed along with the tender.

3. Tenders should be submitted in special forms which can be obtained from the Senior Executive Engineer, Mysore Railways, Mysore, on payment of rupee one, which amount is not refunable under any circumstances.

4. Tenders which give rates, as per estimate rates or so much per cent above or below estimate rates will not be considered. The rates should be noted both in figures and words.

5. The name of the accepted tenderer will be posted on the Notice Board of the Senior Executive Engineer's Office as soon as it is approved by the Superintendent, Way and Works, Mysore Railways. No enquiries regarding the acceptance or rejection of a tender will be replied.

6. The earnest money of the unsuccessful tenderers will be returned as soon as possible after the tenders are disposed of, while that of the successful tenderer will be accepted as part payment towards the security deposit due as per para 7 *infra*.

7. The successful tenderer should deposit with the Auditor, Mysore Railways, Mysore, before he signs the Schedule Agreement. 5 per cent of the value of the work for which the tender is accepted as security for due fulfilment of the terms of the Agreement.

8. The final acceptance of the tender will rest with the Superintendent, Way and Works, Mysore Railways, Mysore, who does not bind himself to accept the lowest or any tender and who further reserves to himself the right to reject, without assigning any reasons therefor, any or all the tenders.

9. Successful tenderers should execute within eight days of the date of notification of acceptance of tenders, the usual Railway Schedule Agreement. Failure to comply with this condition will render the contract null and void and the earnest money forfeited.

10. Work should be started within two weeks from the date of acceptance of tender and completed within three months from the date of orders to start the work, with a guaranteed monthly rate of progress. The accompanying schedule gives the approximate quantity of works and this quantity is not guaranteed.

11. The time limit specified in para 10 should be strictly adhered to and any violation of this will render the contractor liable to forfeit his 5 per cent deposit amount not as a penalty but as ascertained and liquidated damages recoverable accordingly.

12. Plans and specifications and other details of work to be done are available for inspection in the Senior Executive Engineer's Office, Mysore Railways, Mysore, where intending tenderers may call and obtain required information during office hours.

13. In all matters of dispute regarding rates, measurements quality of work, etc., and in all disputes of any kind, the decision of the Superintendent, Way and Works, Mysore Railways, will be final and legally binding.

14. Contractors should make their own arrangements for water required for the work and Departmental water will not be spplied.

Schedule.

Sl. No.	Particulars	Per	Quantity
1	Earthwork excavation in all soils including blasting hard rock and conveying the spoil to adjacent bank with a lead of 1500 feet and levelling.	1,000 C.ft.	25,500 C.ft.
2	Concrete broken stone in sand mortar ...	100 ,,	5,100 ,,
3	Coursed rubble masonry in sand mortar first ...	100 ,,	5,560 ,,
4	Burnt stone slabs 6" thick dressed and fixed in mortar ..	S.ft.	125 S.ft.
5	Burnt stone slabs 4" thick two lines dressed and chamfered and fixed in sand mortar.	,,	26 ,,
6	Cement concrete bed blocks (1 cement : 2 sand : and 4 stone jelly) plastering ½" thick with cement alround, fixing rag bolts (supplied departmentally) including charges for making necessary framework required for laying	C.ft.	340 C.ft.

Sl. No.	Particulars	Per	Quantity
7	Flooring with 6" thick concrete, broken stone in sand mortar, and cement plastering ½" thick.	Sqr	775 S.ft.
8	Cement pointing	„	2,100 „
9	Laying and jointing stoneware pipes 12" in diameter, filling in earth, watering and tamping, etc., complete.	R.ft.	300 R.ft.
10	Supplying and fixing steel shutters ½" thick with hinges, etc., complete.	S.ft.	60 S.ft.
11	Fixing cast iron standards including fixing of holding down bolts in concrete bed, etc., complete.	No.	14
12	Dismantling stone masonry, inserting 6" thick stone sills and lintels and pipes and rebuilding the gaps, cement pointing, etc., complete.	„	3
13	Removing and refixing burnt stone slabs in sand mortar ...	S.ft.	10 S.ft.
14	Flooring with concrete, broken stone in cement mortar 6" thick and ¾" thick cement plastering.	Sqr.	700 „

MYSORE DIVISION (Open Lines).

Notification, dated 2nd August 1933.

Notice is hereby given that sealed tenders for either Schedule A or B or both A and B will be received at the Office of the Senior Executive Engineer, Open Line Division, Mysore Railways, Mysore, up to 4 P.M. on the 25th August 1933, from Contractors who are willing to do the work of construction of extension of New Machine Shop in the Central Workshops area.

2. Every tender must be accompanied by an earnest money as noted below against each Schedule which should be paid to the Auditor, Mysore Railways, Mysore, and the receipt thereof enclosed along with the tender.

3. Tenders should be submitted in special forms which can be obtained from the Senior Executive Engineer, Mysore Railways, Mysore, on payment of rupee one, which amount is not refundable under any circumstances.

4. Tenders which give rates, as per estimate rates or so much per cent above or below estimate rates will not be considered. The rates should be noted both in figures and words.

5. The name of the accepted tenderer will be posted on the Notice Board of the Senior Executive Engineer's Office as soon as it is approved by the Superintendent, Way and Works, Mysore Railways, Mysore. No enquiries regarding the acceptance or rejection of a tender will be replied.

6. The earnest money of the unsuccessful tenderers will be returned as soon as possible after the tenders are disposed of while that of the successful tenderer will be accepted as part payment towards the security deposit due as per Para 7 *infra*.

7. The successful tenderer should deposit with the Auditor, Mysore Railways, Mysore, before he signs the schedule agreement, five per cent of the value of the work for which the tender is accepted as security for due fulfilment of the terms of the agreement.

8. The final acceptance of the tender will rest with the Superintendent, Way and Works, Mysore Railways, Mysore, who does not bind himself to accept the lowest or any tender and who further reserves to himself the right to reject, without assigning any reasons therefor, any or all the tenders.

9. Successful tenderers should execute within eight days of the date of notification of acceptance of tenders, the usual Railway Schedule Agreement. Failure to comply with this condition will render the contract null and void and the earnest money forfeited.

10. Work should be started within two weeks from the date of acceptance of tender and completed as noted below, with a guaranteed monthly rate of progress. The accompanying schedule gives the approximate quantity of works and this quantity is not guaranteed.

11. The time limit specified in para 10 should be strictly adhered to and any violation of this will render the contractor liable to forfeit his five per cent deposit amount not as a penalty but as ascertained and liquidated damages recoverable accordingly.

12. Plans and specifications and other details of work to be done or available for inspection in the Senior Executive Engineer's Office, Mysore Railways, Mysore, where intending tenderers may call and obtain required information during office hours.

13. In all matters of dispute regarding rates, measurement, quality of work, etc., and in all disputes of any kind, the decision of the Superintendent, Way and Works, Mysore

SCHEDULE A.

(The earnest money for this portion of work is rupees five hundred and the work should be completed within five months from the date of orders to start the work.)

Sl. No.	Particulars	Per	Quantity
1	Earth work excavation in all soils including blasting hard rock and conveying the spoil to adjacent bank with a lead of 1,500 feet.	1,000 C.ft.	35,700 C.ft.
2	Concrete broken stone in sand mortar ...	100 „	2,850 „
3	Concrete in cement mortar including wooden moulds, lift and fixing of holding down bolts.	„	200 „
4	Dismantling stone masonry and removing the spoil to adjacent bank including a lead of 500 feet.	„	„
5	Dismantling brick masonry and removing the spoil to adjacent bank including a lead of 500 feet.	„	„
6	Coursed rubble masonry in sand mortar first sort with Departmental stones.	„	100 „
7	Coursed rubble masonry first sort in sand mortar with new stones including dressing corner stones of walls, pilaster and jambs of doorways and windows, etc.	„	12,850 „
8	Coursed rubble masonry first sort in cement mortar including dressing corner stones of pilasters.	100 C.ft.	560 C.ft.
9	Coursed rubble masonry first sort, cut stone arch work in sand mortar including centering charges.	„	70 „
10	Burnt stone slabs 6" thick dressed and fixed in sand mortar.	S.ft.	600 S.ft.
11	Cornice and coping cement concrete slabs as per approved design including cement plastering, hoisting and fixing in position in sand mortar.	C.ft.	700 C.ft.
12	Dismantling cornice, 9" thick two courses of burnt stone slabs, conveying, hoisting and fixing them in position in sand mortar including cement pointing etc., complete.	R.ft.	70 R.ft.
13	Conveying, hoisting and fixing in position including necessary assembling, rivetting, etc., complete lintel girders over doorways.	Cwt.	65 Cwts.
14	Conveying, hoisting and fixing in position including necessary assembling, rivetting, etc., complete, Steel rolling shutters (13' x 15' see plan) suitable large doorways in Workshops.	S.ft.	756 S.ft.
15	Conveying, hoisting and fixing in position including necessary assembling, rivetting, etc., complete Louvre or other type of steel windows, including fixing of glass panes with contractor's putty (glass panes will be supplied by Government).	„	720 „
16	Cement pointing	Sqr.	13,500 „
17	Cement plastering ¾" thick including scaffolding charges.	„	200 „
18	Flooring with 6" thick concrete broken stone in cement mortar and ½" thick cement plastering.	„	1,035 „
19	Silicate painting, two coats	„	10,200 „
20	Dismantling coping burnt stone slabs, conveying and fixing the same in new position in sand mortar including cement pointing.	S.ft.	120 „

SCHEDULE B.

(The earnest money for this portion of work is Rs. 200 and the work should be completed within two months from the date of orders to start the work.)

Sl. No.	Particulars	Per	Quantity
1	Conveying, hoisting and fixing in position including necessary assembling, rivetting, etc., complete lattice girders 69 feet over all length.	Each	2
2	Conveying, hoisting and fixing in position including necessary assembling, rivetting, etc., complete R. S. I. purling, angle iron runners, etc.	Cwt.	125 Cwts.
3	Conveying, hoisting and fixing in position including necessary assembling, rivetting, etc., complete R. S. Trusses for 35 feet span including North light arrangements.	Each	15
4	Conveying, hoisting and fixing in position including necessary assembling, rivetting, etc., complete Crittal or other type of steel windows for North light including fixing Departmental glass panes with Contractor's putty, etc., complete.	S.ft.	700 S.ft.
5	Conveying, hoisting and fixing in position 22 B. W. G. galvanised iron corrugated sheets including wind ties, ridging, etc., complete.	Sqr.	8,600 „
6	Conveying, hoisting and fixing in position 22 B. W. G. galvanised iron gutters 12" wide including fixing of brackets, soldering, etc., complete.	R.ft.	218 R.ft.
7	Conveying, hoisting and fixing in position cast iron down water pipes 4" diameter including fixing supports in stone masonry.	„	138 „
8	Removing galvanised iron corrugated roofing sheets and refixing the same in new positions.	Sqr.	500 S.ft.
9	Removing galvanised iron gutters and refixing the same in new position including fixing of brackets.	R.ft.	73 R.ft.
10	Removing down water pipes and refixing the same in new position including fixing of supports in stone masonry.	„	38 „
11	Unloading materials from wagons and stacking including a lead of 300 feet.	Ton	100 Tons

Specification for works will be according to Marryat's Hand Book, Volume I.

R. N. MIRZA,
Senior Executive Engineer.

EXECUTIVE ENGINEER'S OFFICE, MYSORE RAILWAYS, MYSORE.

Abstract Notification, dated 4th August 1933.

The attention of the public is invited to the detailed notification calling for tenders for the Construction of Compound Wall in the Central Work Shop area, published on pages 956–957 of Part VI of the *Mysore Gazette*, dated 3rd August 1933.

R. N. MIRZA,
Senior Executive Engineer.

MISCELLANEOUS DEPARTMENTS

DEPARTMENT OF AGRICULTURE, MYSORE STATE.

OFFICE OF THE MANAGER, GOVERNMENT EXPERIMENTAL FARM, HEBBAL.

Abstract Notification, dated 24th July 1933.

Sealed tenders will be received by the Manager, Government Experimental Farm, Hebbal up to 11 A.M. on Monday the 14th August 1933, for the supply of Cattle Feed and Miscellaneous Articles required for the year 1933-34 for this Farm.

For further particulars *vide* Notificati[illegible]